

1513/ADVS/GS (Edn)

20 Apr 2026

CALLING FOR QUOTATIONS

Dear Sir,

1. The quotations are hereby invited from vendors/dealers/contractors with varied experience in the field of construction work.
2. The quotations are required as following :-

S No	Description of wk	Qty	Remarks
(a)	Renovation of washroom (size 8.4' x 7.6') after dismantling of centre wall (01 x EWC, 01 Vanity Basin incl plumbing, tiling(floor tiling & wall tiling upto 5' height), painting, electrical work & replacement of door & windows) (As per scope of work)	01 Job	

3. The sealed Bids are required to be addressed to Principal, ADVS Beas and to be deposited before 1100 hrs on **28 Apr 2026**. The sealed quotation box is available at the main gate of HQ 55 (I) Mech Bde on all working days from 0800 hrs to 1400hrs.
4. No cutting on any figures will be accepted. The vendors/firms are at liberty to be present during bid opening for fair & transparent bidding.
5. **Validity of quotations.** The quotations will be valid for at least 3 months from the date of opening.
6. **Date & time for completion of work.** The work is required to be completed within **20** working days from the issue of supply order.
7. **Force majeure.** The school will not be responsible for any untoward / unforeseen reqmt as generated at the vendor's end.
8. **Payments.** The payments will be made by the school within seven days after inspection of work at ADVS Beas.
9. **Demurrage.** Late work schedule will be charged demurrage @ 0.5% per week for delayed time schedule of the project cost.
10. **Manufacturing guarantee / warranty.** The contractor firm will be responsible for any defect or maintenance or low quality work / performance / material if found any during inspection by the auth of the school. Adequate charges will be levied from the bills paid by the school. The school deserves the right to cancel / modify the supply order / schedule of work at any stage as per requirement of the school.

Rupali Sehgal
(Mrs Rupali Sehgal)
Principal

SCOPE OF WORK

Name of Work :- Renovation of washroom of Principal office.

1. The project involves complete renovation and upgrading of the existing washroom of Principal's office. The objective is to improve functionality, hygiene, aesthetics, and durability using modern fixtures and finishes.

2. Demolition & Removal

- Dismantling and removal of existing sanitary fixtures (WC, wash basin, taps, etc.)
- Removal of existing wall and floor tiles
- Dismantling of damaged plumbing lines and fittings

3. Civil & Structural Work

- Repair of wall, floor, and ceiling surface
- Plastering and leveling of surfaces to prepare for tiling
- Minor masonry work if layout adjustments are required

4. Plumbing Works

- Installation of new water supply lines (hot and cold, if applicable)
- Installation of new drainage and waste pipes

5. Electrical Works

- Rewiring. Fitting of Wall Fan (Make Orient/Bajaj)
- Installation of new switches, sockets, and exhaust fan point
- Provision for mirror light and general lighting
- Ensuring proper earthing and safety compliance

6. Tiling Works

- Supply and installation of anti-skid floor tiles
- Installation of ceramic/vitrified wall tiles up to full height or specified level
- Proper grouting and finishing

7. Sanitary Fixtures & Fittings

- Installation of new WC (Western style)
- Wash basin with vanity (if required)
- Mirror, towel rod/ring, soap dispenser, and other fittings

8. Ceiling Work

- Installation of false ceiling (PVC/Gypsum)
- Provision for light fixtures and ventilation

9. Painting & Finishing

- Painting of non-tiled wall areas with moisture-resistant paint
- Silicone sealing at joints to prevent seepage

10. Ventilation & Exhaust

- Installation of exhaust fan (Orient/Bajaj). Replacement of wooden window with Aluminium Windows Ensuring proper ventilation system

11. Door & Accessories

- Replacement of wooden door with Aluminium Door.

13. Timeline

- Estimated project duration: 15 days

14. Quality & Safety

- All materials to be of approved quality and standard brands
- Work to comply with safety norms and building regulations

Rupali Sehgal
Principal
Army Double Victory School
Beas (Amritsar)